

Day work, traffic changes and parking restrictions to install ground monitoring equipment on Balmain Road

Day work will be carried out on Balmain Road, near the intersection with Point Street, to install ground monitoring equipment. This work will involve a stop/slow traffic set up and temporary parking restrictions.

What we're doing

Tunnelling for the Rozelle Interchange project is underway, and an important part of this work involves regularly monitoring the surface for any movement during and after excavation. Data is collected from monitoring instruments at fixed points both close to and at a distance from the tunnel alignment (to provide broader context) including the intersection of Balmain Road and Point Street. **Installation of monitoring equipment is not an indication that tunnelling for the Rozelle Interchange project is occurring at this location.**

From **Thursday 24 September to Monday 28 September, excluding the weekend**, we'll be installing Shape Acceleration Arrays (SAA) on Balmain Road, near the Point Street intersection, as shown on the map over the page. SAA is a type of monitoring equipment that facilitates automatic and remote data collections and will remain in place till project end.

SSA monitoring equipment consists of a pole measuring approximately 2.5 metres, a battery and solar panel as shown in the image below.



When

Thursday 24 September
Friday 25 September and
Monday 28 September

Hours of operation

Between 7am and 6pm

Where

Balmain Road near the intersection with Point Street, Lilyfield

Community Information Centre

We're following the NSW Health 'social distancing' guidelines and the centre is closed until we're able to

We speak your language



Need an interpreter?
Call the Translating and Interpreting Service on
131 450.

Notification No. 161

What work is required

The installation of SAA monitoring equipment will involve trenching the road, excavating the footpath, installing a pole, battery and solar panel, running a conduit and cable through trench and commissioning work. The ground is then backfilled and reinstated. This activity is expected to take three days to complete on **Thursday 24 September, Friday 25 September and Monday 28 September**.

A temporary work site will be established on Balmain Road for the installation work. The temporary work site will demobilise at the end of each day.

How this affects you

Temporary on-street parking restrictions (between 3-6 spaces) will be in place along Balmain Road, prior to installation work starting from **Thursday 24 September** and for the duration of the work. Parking will be returned once the work has been completed.

A stop/slow traffic set up will be in place at the intersection of Balmain Road and Point Street during daytime hours. Two-way traffic will be maintained at the intersection under the direction of traffic control, however, please expect delays when travelling in the area.




Equipment used for this work include, but is not limited to, vacuum trucks, road saw, compactor, assorted power tools, hand tools, light vehicles and traffic control. This work is expected to generate high noise, particularly when the vacuum truck and raw saw are in use.

If you have a question about this work, please call 1800 660 248 and ask to speak to a member of the Rozelle Interchange community relations team or email info@rozelleinterchange.com.au.

Approximate work location on Thursday 24 September, Friday 25 September and Monday 28 September



Legend

-  Work location
-  Two-way traffic maintained under the direction of traffic control. Please expect delays.
-  Temporary on-street parking restrictions